




NOTE:

- SUPPLY, INSTALLATION, AND CONFIGURATION OF CNS EQUIPMENT (NETWORK SWITCHES, FIREWALL AND WIRELESS ACCESS POINT) BY EMAAR IT.
- SUPPLY, INSTALLATION AND LABELLING OF PATCH CORDS BY SCS CONTRACTOR.
- ALL CONTRACTORS SHALL AGREE WITH THE EMPLOYER'S IP SCHEME.
- THE CORE SWITCHES SHALL BE EQUIPPED WITH A REDUNDANT POWER SUPPLY UNIT, N+1 PSU.
- ALL SWITCHES SHALL BE MOUNTABLE IN A STANDARD 19" RACK WITH THE MOUNTING KIT INCLUDED.
- ALL SWITCHES SHALL PROVIDE FUNCTIONALITY FOR SWITCH PORT MIRRORING OR PORT MONITORING.
- THE CORE SWITCH SHALL BE ABLE TO PROVIDE LAYER 2 SWITCHING AND LAYER 3 ROUTING FUNCTION.
- THE CORE SWITCH SHALL SUPPORT AT LEAST 200 GBPS SWITCHING CAPACITY AND THROUGHPUT OF 150 MPPS (MEGA-PACKET PER SECOND) IN HARDWARE FOR LAYER 2 TO LAYER 4 TRAFFIC.
- NEXT GENERATION FIREWALL, AVERAGE THROUGHPUT SHALL BE MINIMUM OF 1 GBPS.
- IP-SEC THROUGHOUT MINIMUM OF 500MBPS.
- THE FIREWALL SHALL SUPPORT IPS FUNCTIONALITIES WITH MINIMAL IMPACT ON FIREWALL AND VPN SERVICES THROUGHPUT.
- THE PROPOSED FIREWALL SHOULD BE CAPABLE OF MANAGING FROM EMAAR'S CENTRALIZED FIREWALL MANAGEMENT CONSOLE.
- WAP SHOULD BE CONTROLLER BASED FOR EASE OF MONITORING AND CONTROL.
- ALL WAPS SHOULD REGISTER WITH EMAAR'S CENTRALIZED WLAN CONTROLLER.
- THE WLAN ACCESS POINT (AP) IS DESIGNED TO SUPPORT BOTH EXISTING 802.11A/B/G/N/AC AND ALLOW WIRELESS ACCESS IN BOTH 2.4GHZ AND 5GHZ FREQUENCY.
- THE WLAN AP SHALL BE WALL/CEILING -MOUNTABLE.
- THE WLAN AP SHALL ALLOW SIMULTANEOUS OPERATION OF 2.4GHZ AND 5GHZ WIRELESS NETWORKS.
- THE WLAN AP SHALL SUPPORT MIN 2X2 MIMO TECHNOLOGY, MAYBE 3X3 OR 4X4 MIMO IN HIGHLY DENSE PUBLIC AREAS.
- ALL WAPS SHOULD HAVE THE NECESSARY LICENSES TO ADD WITH CORPORATE CONTROLLER.
- ALL ACCESS SWITCHES SHALL BE CONNECTED DIRECTLY TO CORE SWITCH.
- 20% SPARE PORT CAPACITY SHALL BE CONSIDERED IN CORE AND ACCESS NETWORK SWITCHES.




Key Plan



General Notes

- Do not Scale The Drawings. Follow (The MM) Written Dimensions Unless Otherwise Mentioned.
- Each Drawing Shall be Read in Conjunction With all Other Drawings, Specification & the General Standard Details. In Case of Any Discrepancies Bring it to the Knowledge of Engineer and Same to be Resolved Prior to Execution of Work.
- Dimensions Shown on These Drawings are Structural Dimensions, Unless Noted Otherwise.
- All Levels Indicated On These Drawings are Levels as per the Survey Datum, Same Should be Verified at Site Prior to Execution of Work.
- All Levels Indicated On These Drawings are Based On Design Level, Which is Equivalent to Datum Level and Same Should be Verified at Site Prior to Execution of Work.



No.	Date	Initials	Description
09	10/03/2026	JP	TENDER SUBMISSION

REVISIONS / ISSUE

THIS DRAWING MUST NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE PRIOR APPROVAL OF ARIF & BINTOAK

TENDER SUBMISSION



Project Title:

Proposed Residential Townhouses and Standalone Villas TH-1, TH-2, and TH-3 at Grand Polo Club & Resort, Dubai, UAE

Discipline :	ICT
Drawing title:	ACTIVE NETWORK SWITCH SINGLE LINE DIAGRAM COMMUNITY CENTER - TH-01

Architectural Engineer	Electrical Engineer	Structural Engineer
MUSTAFA ABID	MARWAN MOHD.	RIHAM RAMADAN
Registration # 5847	Registration # 80102	Registration # 105082
Scale(s): NTS	Date drawn: 10/03/2026	Project no: 1857
Drawn by: JP	Checked : MM	Approved : JR
Drawing Number :	GPCR-TH01-IES-CC1-SLD-ICT-IT-2001-00	