



NOTE:

- SUPPLY, INSTALLATION, AND CONFIGURATION OF CNS EQUIPMENT (NETWORK SWITCHES, FIREWALL AND WIRELESS ACCESS POINT) BY EMAAR IT.
- SUPPLY, INSTALLATION AND LABELLING OF PATCH CORDS BY SCS CONTRACTOR.
- ALL CONTRACTORS SHALL AGREE WITH THE EMPLOYER'S IP SCHEME.
- THE CORE SWITCHES SHALL BE EQUIPPED WITH A REDUNDANT POWER SUPPLY UNIT, N+1 PSU.
- ALL SWITCHES SHALL BE MOUNTABLE IN A STANDARD 19" RACK WITH THE MOUNTING KIT INCLUDED.
- ALL SWITCHES SHALL PROVIDE FUNCTIONALITY FOR SWITCH PORT MIRRORING OR PORT MONITORING.
- THE CORE SWITCH SHALL BE ABLE TO PROVIDE LAYER 2 SWITCHING AND LAYER 3 ROUTING FUNCTION.
- THE CORE SWITCH SHALL SUPPORT AT LEAST 200 GBPS SWITCHING CAPACITY AND THROUGHPUT OF 150 MPPS (MEGA-PACKET PER SECOND) IN HARDWARE FOR LAYER 2 TO LAYER 4 TRAFFIC.
- NEXT GENERATION FIREWALL, AVERAGE THROUGHPUT SHALL BE MINIMUM OF 1 GBPS.
- IP-SEC THROUGHOUT MINIMUM OF 500MBPS,
- THE FIREWALL SHALL SUPPORT IPS FUNCTIONALITIES WITH MINIMAL IMPACT ON FIREWALL AND VPN SERVICES THROUGHPUT.
- THE PROPOSED FIREWALL SHOULD BE CAPABLE OF MANAGING FROM EMAAR'S CENTRALIZED FIREWALL MANAGEMENT CONSOLE.
- WAP SHOULD BE CONTROLLER BASED FOR EASE OF MONITORING AND CONTROL.
- ALL WAPS SHOULD REGISTER WITH EMAAR'S CENTRALIZED WLAN CONTROLLER.
- THE WLAN ACCESS POINT (AP) IS DESIGNED TO SUPPORT BOTH EXISTING 802.11A/B/G/N/AC AND ALLOW WIRELESS ACCESS IN BOTH 2.4GHZ AND 5GHZ FREQUENCY.
- THE WLAN AP SHALL BE WALL/CEILING- MOUNTABLE.
- THE WLAN AP SHALL ALLOW SIMULTANEOUS OPERATION OF 2.4GHZ AND 5GHZ WIRELESS NETWORKS.
- THE WLAN AP SHALL SUPPORT MIN 2X2 MIMO TECHNOLOGY, MAYBE 3X3 OR 4X4 MIMO IN HIGHLY DENSE PUBLIC AREAS.
- ALL WAPS SHOULD HAVE THE NECESSARY LICENSES TO ADD WITH CORPORATE CONTROLLER.
- ALL ACCESS SWITCHES SHALL BE CONNECTED DIRECTLY TO CORE SWITCH.
- 20% SPARE PORT CAPACITY SHALL BE CONSIDERED IN CORE AND ACCESS NETWORK SWITCHES.



Key Plan



General Notes :

- Do not Scale The Drawings. Follow (The MM) Written Dimensions Unless Otherwise Mentioned.
- Each Drawing Shall be Read in Conjunction With all Other Drawings, Specification & the General Standard Details. In Case of Any Discrepancies Bring it to the Knowledge of Engineer and Same to be Resolved Prior to Execution of Work.
- Dimensions Shown on These Drawings are Structural Dimensions. Unless Noted Otherwise.
- All Levels Indicated On These Drawings are Levels as per the the Survey Datum, Same Should be Verified at Site Prior to Execution of Work.
- All Levels Indicated On These Drawings are Based On Design Level, Which is Equivalent to Datum Level and Same Should be Verified at Site Prior to Execution of Work.



| No. | Date       | Initials | Description       |
|-----|------------|----------|-------------------|
| 01  | 10/03/2026 | JP       | TENDER SUBMISSION |

REVISIONS / ISSUE

THIS DRAWING MUST NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE PRIOR APPROVAL OF ARIF & BINTOAK

TENDER SUBMISSION



Project Title:

Proposed Residential Townhouses and Standalone Villas TH-1, TH-2, and TH-3 at Grand Polo Club & Resort, Dubai, UAE

Discipline : ICT

Drawing title:  
ACTIVE NETWORK SWITCH  
SINGLE LINE DIAGRAM  
COMMUNITY CENTER - TH-02

| Architectural Engineer | Electrical Engineer       | Structural Engineer   |
|------------------------|---------------------------|-----------------------|
| MUSTAFA ABID           | MARWAN MOHD.              | RIHAM RAMADAN         |
| Registration # 5847    | Registration # 80102      | Registration # 105082 |
| Scale(s):<br>NTS       | Date drawn:<br>10/03/2026 | Project no:<br>1857   |
| Drawn by:<br>JP        | Checked:<br>MM            | Approved:<br>JR       |

Drawing Number : GPCR-TH02-IES-CC2-SLD-ICT-IT-2001-00