

PROJECT: GRAND POLO CLUB & RESORT
DB REF: MDB-CC
FED FROM:

DETAILS OF CONNECTED LOAD / MAX. DEMAND

Client: EMAAR
Consultant: **Arif & Bintok** consulting architects & engineers

AREA: Dubai South
PLOT NO: TH01,TH02&TH03
LOCATION: ELECTRICAL CABINET

SR.	CIRCUIT / FEEDER DB NO.	SP	TP	RATING - AMPS			Fault Duty kA	PVC/ XLPE	CABLE SIZE		ECC SIZE 1C, mm ²	CONNECTED LOAD - kW				PROPOSED kWh METERING				REMARKS	
				F/S ISO	MCCB ACB	MCB		SWA/ PVC	2/4 x 1C mm ²	2/3/4C mm ²		R-PH kW	Y-PH kW	B-PH kW	TOTAL kW	1-PH (1)	3-PH (2)	3-PH (3)	CT (4)		
	INCOMER				400 (N/A)			XLPE		1X4C 300	1X1C 150	74.00	73.40	72.60	220.00				1	400/5A CT	
	OUTGOING																				
1	DB-CH		X		63		25	XLPE		4Cx16	1Cx16	7.20	7.43	7.04	21.67						
2	DB-SB		X		63		25	XLPE		4Cx16	1Cx16	9.63	8.01	8.75	26.39						
3	DB-GYM		X		80		25	XLPE		4Cx25	1Cx16	13.10	11.96	13.28	38.34						
4	DB-PUMP ROOM		X		40		25	XLPE		4Cx10	1Cx10	2.08	4.00	1.53	7.61						
5	MAIN SWIMMING POOL		X		200		25	XLPE		4Cx95	1Cx50	26.67	26.67	26.67	80.00					30mA ELCB	
6	KIDS SWIMMING POOL		X		63		25	XLPE		4Cx16	1Cx16	5.00	5.00	5.00	15.00					30mA ELCB	
7	SPLASH PAD SWIMMING POOL		X		40		25	XLPE		4Cx16	1Cx16	5.00	5.00	5.00	15.00					30mA ELCB	
8	LANDSCAPE LIGHTING		X		40		25	XLPE				2.00	2.00	2.00	6.00					30mA ELCB	
9	CAPACITOR BANK		X		160		25	XLPE		4Cx70	1Cx35									70 KVAR	
10	SPARE		X		40							3.33	3.33	3.33	10.00						
	NOTE(S):		1	ALL MCCB's BEFORE TARIFF METERING SHALL HAVE PADLOCKING FACILITY AT ITS 'OFF' POSITION																	
MDB CONNECTED TO : DEWA LV DB/TRANSF							TOTAL CONNECTED LOAD PER PHASE					74.00	73.40	72.60	220.00						
SMDB CONNECTED TO : MDB.....																					
MAX. DEMAND LOAD (3 PH) AT 90% DIVERSITY =				198.00 kw				TOTAL CONNECTED LOAD (3 PH) =				220.00 kw									
CONTRACTOR : TEL:.....																					
										(1) Upto 60A (1 Phase)		(2) Upto 100A (3 Phase)		(3) 125-160A		(4) LV CTA / HV CTA					



LOAD DISTRIBUTION SCHEDULE

Project : GRAND POLO CLUB & RESORT
 Proj. No. : 1857
 DB No. : DB-CH
 Fed From : MDB-CC

CLIENT: EMAAR
 Consultant: Arif & Bintok consulting architects & engineers
 (3-PHASE XR YM)

Area : Dubai South
 Plot No. TH01,TH02&TH03
 Locati : COMMUNITY HALL

RATING OF INCOMER	RATING OF ELCB	SL NO	CIR NO	MCB RTG. IN AMPS	CCT WIRE SIZE mm²	ECC WIRE SIZE mm²	ROOM / AREA	CONNECTED LOAD / POINTS																WATT / UNIT	LOAD PER CIRCUIT WATTS			REMARKS
								LTG	STRIP LIGHT	EX FAN	13A SSO	13A TSO	SH S/O	SPUR	WH	HD	20A S/O	20A SKT	FCU	CU	ISOL	R	Y		B			
63A TP ISOL	40A, 4P 100mA ELCB-1	1	R1	10	2.5	2.5	COMMUNITY HALL	10														15	165			LIGHTINGS		
		2	Y1	10	2.5	2.5	COMMUNITY HALL	10														15/20		205		LIGHTINGS		
		3	B1	10	2.5	2.5	COMMUNITY HALL		68.0													10			680	LIGHTINGS		
		4	R2	10	2.5	2.5	EXTERNAL + ROOF	4 / 2														15/15	90			LIGHTINGS		
		5	Y2	10	2.5	2.5	COMMUNITY HALL	7														50		350		LIGHTINGS		
		6	B2				SPACE																					
	40A, 4P 30mA ELCB-2	7	R3	20	4.0	4.0	COMMUNITY HALL					1										400	400			FRIDGE WITH DP SWITCH		
		8	Y3	20	4.0	4.0	COMMUNITY HALL					1										400		400		TV		
		9	B3	20	4.0	4.0	COMMUNITY HALL					1										400			400	DB		
		10	R4	20	4.0	4.0	COMMUNITY HALL					3										100	300			WIFI		
		11	Y4	20	4.0	4.0	COMMUNITY HALL					1										200		200		EXTERNAL AREA		
		12	B4	32	4.0	4.0	COMMUNITY HALL									1						100		100		ACP @ H/L		
	40A, 4P 30mA ELCB-3	13	R5	20	4.0	4.0	COMMUNITY HALL					1	3									200 / 400	1400			RING CIRCUIT		
		14	Y5	20	4.0	4.0	COMMUNITY HALL					2										400		800				
		15	B5	32	4.0	4.0	COMMUNITY HALL					3										400		1200		RING CIRCUIT		
		16	R6	20	4.0	4.0	COMMUNITY HALL									1						100	100			ACP @ H/L		
		17	Y6	20	4.0	4.0	COMMUNITY HALL									1						200		200		MOTORIZED BLINDS		
		18	B6	20	6.0	6.0	COMMUNITY HALL ROOF												1			370			370	EAF -02		
	40A, 4P 30mA ELCB-4	19	R7	20	4.0	4.0	ROOF					1										200	200					
		20	Y7	20	4.0	4.0	COMMUNITY HALL					5										200		1000		TBALE SOCKET (RING)		
		21	B7	20	4.0	4.0	COMMUNITY HALL					1										200		200		PROVISION FOR SCENT DIFFUSER		
		22	R8				SPACE																					
		23	Y8	20	4.0	4.0	COMMUNITY HALL							3								50		150		SCENT DIFFUSER		
		24	B8				SPACE																					
	40A, 4P 100mA ELCB-5	25	R9	32	6.0	6.0	COMMUNITY HALL ODU- GF-01													1		4090	4090			UVR+TIMER+CONT.		
		26	Y9	32	6.0	6.0	COMMUNITY HALL ODU- GF-02													1		4090		4090			UVR+TIMER+CONT.	
		27	B9	32	6.0	6.0	COMMUNITY HALL ODU- GF-03													1		4090			4090		UVR+TIMER+CONT.	
	40A, 4P 100mA ELCB-6	28	R10	10	2.5	2.5	COMMUNITY HALL	14	24.5													15/ 10	455					
		29	Y10	10	2.5	2.5	COMMUNITY HALL		2													15		30				
		30	B10				SPACE																					
TOTAL (W)																								7200	7425	7040		

CABLE SIZE: 4C 16 mm² XLPE/SWA/PVC/CU +
 1C 16 mm² PVC/CU GY ECC

TOTAL (KW): 21.67

CONSULTANT: ARIF & BINTOK CONSULTING ARCHITECTS & ENGINEERS, P.O.BOX-3670, DUBAI, UAE. TEL-04 3372888, FAX-04 3370352.



LOAD DISTRIBUTION SCHEDULE

Project : GRAND POLO CLUB & RESORT
 Proj. No. : 1857
 DB No. : DB-GYM
 Fed Fron: MDB-CC

CLIENT: EMAAR
 Consultant: **Arif & Bintok** consulting architects & engineers
 (3-PHASE XR YM)

Area : Dubai South
 Plot No. TH01,TH02&TH03
 Loca : GYM

RATING OF INCOME R	RATING OF ELCB	SL NO	CIR NO	MCB RTG. IN AMPS	CCT WIRE SIZE mm²	ECC WIRE SIZE mm²	ROOM / AREA	CONNECTED LOAD / POINTS														WATT / UNIT	LOAD PER CIRCUIT WATTS			REMARKS
								LTG	STRIP LIGHT	EX FAN	13A SSO	13A TSO	SH S/O	KIT HD	WH	HD	13A SPUR	IND SKT	ISOL	R	Y		B			
80A TP ISOL	40A, 4P 100mA ELCB-1	1	R1	10	2.5	2.5	GYM	9											15	270			LIGHTINGS			
		2	Y1	10	2.5	2.5	GYM + YOGA		23										15		345		LIGHTINGS			
		3	B1	10	2.5	2.5	YOGA	9											15			135	LIGHTINGS			
		4	R2	10	2.5	2.5	YOGA	9											15	135			LIGHTINGS			
		5	Y2	10	2.5	2.5	GYM		46										15		690		LIGHTINGS			
	40A, 4P 30mA ELCB-2	6	B2	10	2.5	2.5	EXTERNAL + ROOF	6/4											150			120	LIGHTINGS			
		7	R3	20	4.0	4.0	GYM												400	800			TV			
		8	Y3	20	4.0	4.0	GYM				1	2							200 / 400		1000					
		9	B3	20	4.0	4.0	GYM FLOOR SOCKET				8								200			1600	FLOOR BOX			
		10	R4	20	4.0	4.0	GYM										1		100	100			ACP @ H/L			
		11	Y4	20	4.0	4.0	GYM				1	2							200 / 400		1000			RING CIRCUIT		
	40A, 4P 30mA ELCB-3	12	B4	20	4.0	4.0	EXTERNAL				2								200			400				
		13	R5	20	4.0	4.0	GYM, YOGA & EXTERNAL										4		100	400			FOR WIFI			
		14	Y5	20	4.0	4.0	YOGA					2							400		800			DB & GENERAL		
		15	B5	20	4.0	4.0	YOGA										1		100			100	FOR ACP @ H/L			
		16	R6	20	4.0	4.0	GYM										3		200	600			MOTORIZED BLINDS			
		17	Y6	20	4.0	4.0	YOGA					2							400		800					
	40A, 4P 100mA ELCB-4	18	B6	20	4.0	4.0	ROOF				1								200			200				
		19	R7				ROOF FLOOR FOR CU- GYM-01												1	4750	1583			UVR+TIMER+CONT.		
		20	Y7	40	10.0	10.0																1583				
	40A, 4P 100mA ELCB-5	21	B7																				1583			
		22	R8				ROOF FLOOR FOR CU- GYM-02												1	4750	1583			UVR+TIMER+CONT.		
		23	Y8	40	10.0	10.0																1583				
	40A, 4P 100mA ELCB-6	24	B8																				1583			
		25	R9				ROOF FLOOR FOR CU- GYM-03												1	4750	1583			UVR+TIMER+CONT.		
		26	Y9	40	10.0	10.0																1583				
	40A, 4P 100mA ELCB-7	27	B9																				1583			
		28	R10				ROOF FLOOR FOR CU- GYM-04												1	4750	1583			UVR+TIMER+CONT.		
		29	Y10	40	10.0	10.0																1583				
	40A, 4P 100mA ELCB-8	30	B10																				1583			
		31	R11	40	10.0	10.0	ROOF FLOOR FOR CU-YO- 01												1	4090	4090			UVR+TIMER+CONT.		
		32	Y11	20			SPARE													220		220		SPARE		
	40A, 4P 30mA ELCB-9	33	B11	40	10.0	10.0	ROOF FLOOR FOR CU-YO- 02												1	4090			4090	UVR+TIMER+CONT.		
		34	R12	20	6.0	6.0	ROOF FLOOR FOR EAF-01 (YOGA)												1	370	370			FOR EAF-03 (YOGA)		
		35	Y12	20	6.0	6.0	ROOF FLOOR FOR EAF-02 (GYM)												1	370		370		FOR EAF-03 (GYM)		
	40A, 4P 30mA ELCB-10	36	B12	20	4.0	4.0	GYM, YOGA												6	50			300	SCENT DIFFUSER		
		37	R13				SPACE																	SPACE		
		38	Y13	20	4.0	4.0	GYM				1									200		200		BLUETOOTH		
	40A, 4P 30mA ELCB-11	39	B13				SPACE																	SPACE		
		40	R14				SPACE																	SPACE		
		41	Y14	20	4.0	4.0	GYM				1									200		200		BLUETOOTH		
		42	B14				SPACE																	SPACE		
TOTAL (W)																			13098	11958	13278					

CABLE SIZE: 4C 25 mm² XLPE/SWA/PVC/CU +
 1C 16 mm² PVC/CU GY ECC

TOTAL (KW): 38.34

CONSULTANT: ARIF & BINTOK CONSULTING ARCHITECTS & ENGINEERS, P.O.BOX-3670, DUBAI, UAE, TEL-04 3372888, FAX-04 3370352.



LOAD DISTRIBUTION SCHEDULE

Project : GRAND POLO CLUB & RESORT
 Proj. No. : 1857
 DB No. : DB-SB
 Fed From : MDB-CC

CLIENT: EMAAR
 Consultant: Arif & Bintok consulting architects & engineers
 (3-PHASE XR YM)

Area : Dubai South
 Plot No. TH01,TH02&TH03
 Location : Service block

RATING OF INCOMER	RATING OF ELCB	SL NO	CIR NO	MCB RTG. IN AMPS	CCT WIRE SIZE mm²	ECC WIRE SIZE mm²	ROOM / AREA	CONNECTED LOAD / POINTS														WATT / UNIT	LOAD PER CIRCUIT WATTS			REMARKS
								LTG	STRIPLIGHT	EX FAN	13A SSO	13A TSO	13A US	RIT WH	HD	13A SPUR	IND SKT	FCU	CU	ISOL	R		Y	B		
63A TP ISOL	40A, 4P 100mA ELCB-1	1	R1	10	2.5	2.5	MENS WASH ROOM / HANDICAPE TOILET	4/1												10/36	76			LIGHTINGS		
		2	Y1	10	2.5	2.5	WOMEN WASH ROOM	10/5	11											10/10/10		260		LIGHTINGS		
		3	B1	10	2.5	2.5	MENS WASH ROOM / HANDICAPE TOILET	5/3												10/10			80	LIGHTINGS		
		4	R2	10	2.5	2.5	MENS WASH ROOM	5/5	10.5											10/10/10	205			LIGHTINGS		
		5	Y2	10	2.5	2.5	EXTERNAL + ROOF	4/2												15/15			90	LIGHTINGS		
		6	B2	10	2.5	2.5	GARBAGE / STORAGE / MEPI EC	8/1/1												36/10/10			308	LIGHTINGS		
	40A, 4P 30mA ELCB-2	7	R3	20	4.0	4.0	ADA TOILET							1					500	500					HAND DRYER + DP SWITCH	
		8	Y3	20	4.0	4.0	ADA TOILET					3							100			300			FOR SOAP DISP & FLUSH	
		9	B3	20	4.0	4.0	MENS WASH ROOM						1						100				100		TOWEL DISPENSER	
		10	R4	20			SPARE												290	290					SPARE	
		11	Y4	20	4.0	4.0	WOMEN WASH ROOM						1						100			100			TOWEL DISPENSER	
		12	B4	32	4.0	4.0	GARBAGE/ IT RM/ STORAGE/ RESTING RM					2	3						200/400				1600		RING CIRCUIT	
	40A, 4P 30mA ELCB-3	13	R5	20	4.0	4.0	MEN WASHROOM								1				500	500					HAND DRYER + DP SWITCH	
		14	Y5	20	4.0	4.0	WOMEN WASH ROOM								1				500			500			HAND DRYER + DP SWITCH	
		15	B5	32	4.0	4.0	WOMEN WASH ROOM							6					100				600		SENSOR & FLUSH	
		16	R6	32	4.0	4.0	MENS WASH ROOM							9					100	900					SENSOR & FLUSH	
		17	Y6	20	4.0	4.0	HANDICAP TOILET							1					100		100				ACP @ HL	
		18	B6	20	4.0	4.0	SERVICE BLOCK (EXTERNAL)							2					100				200		WIFI	
	40A, 4P 30mA ELCB-4	19	R7	20	4.0	4.0	IT ROOM								1				200	200					FACP	
		20	Y7	20	4.0	4.0	IT ROOM									1			200			200			24x7 PANEL	
		21	B7	20	4.0	4.0	IT ROOM							1					200				200		CMP	
		22	R8	20			SPARE												100	100					SPARE	
		23	Y8	20	4.0	4.0	ROOF						1						200			200				
		24	B8	20	4.0	4.0	MEN & WOMEN WASHROOM, RESTING RM									3			100				100		SCENT DIFFUSER	
	40A, 4P 30mA ELCB-5	25	R9	20	4.0	4.0	ROOF												500	500					ERV-01	
		26	Y9	20			SPARE												100				100		SPARE	
		27	B9				SPACE																			
		28	R10	20	6.0	6.0	ROOF												1	3000	3000				SOLAR WH	
		29	Y10	20	4.0	4.0	GARBAGE ROOM												1	370			370		20A SP ISO. FOR (EAF-05)	
		30	B10	20	6.0	6.0	PROVISION FOR SIGNAGE												1	500				500		PROVISION
	40A, 4P 100mA ELCB-6	31	R11	20			SPARE												100	100					SPARE	
		32	Y11	20	6.0	6.0	ODU-WRKS RST RM												1	1820			1820			UVIR+TIMER+CONT.
		33	B11	20	6.0	6.0	ODU-SB-04 (FOR STORE)												1	1310				1310		UVIR+TIMER+CONT.
		34	R12	20	6.0	6.0	ODU-SB-03 (FOR IT ROOM)												1	1820			1820			UVIR+TIMER+CONT.
		35	Y12	32	6.0	6.0	ODU-SB-01 (FOR MALE WASHROOM)												1	2380			2380			UVIR+TIMER+CONT.
		36	B12	32	6.0	6.0	ODU-SB-02 (FOR FEMALE WASHRM)												1	2370				2370		UVIR+TIMER+CONT.
	40A, 4P 30mA ELCB-8	37	R13	32	6.0	6.0																				
		38	Y13	A	x	x	IT ROOM IT RACK												1	2000				667		15U CABINET (TEL)
		39	B13	TP	6.0	6.0																				
		40	R14	32	6.0	6.0																		667		
		41	Y14	A	x	x	IT ROOM SECURITY RACK												1	2000				667		27U CABINET (CCTV)
		42	B14	TP	6.0	6.0																			667	
	40A, 4P 30mA ELCB-10	43	R15	20			SPARE													100		100				SPARE
		44	Y15	20	4.0	4.0	MEN & WOMEN WASHROOM						1						200			200			50	FLY KILLER
		45	B15	20	4.0	4.0	GARBAGE ROOM							1					50							
		46	R16				SPACE																			
		47	Y16	20	2.5	2.5	MEN & WOMEN WASHROOM	4											15			60				MIRROR LIGHT
		48	B16				SPACE																			
TOTAL (W)																						9625	8014	8752		

CABLE SIZE: 4C 16 mm² XLPE/SWA/PVC/CU +
 1C 16 mm² PVC/CU GY ECC

TOTAL (KW): 26.39

CONSULTANT: ARIF & BINTOK CONSULTING ARCHITECTS & ENGINEERS, P.O.BOX-3670, DUBAI, UAE, TEL-04 3372888, FAX-04 3370352.



LOAD DISTRIBUTION SCHEDULE

Project : GRAND POLO CLUB & RESORT

Proj. No. : 1857

DB No. : DB-PUMP.RM

Fed From : MDB-CC

CLIENT: EMAAR

Consultant: Arif & Bintoak consulting architects & engineers

(3-PHASE XR YM)

Area : Dubai South

Plot No. TH01,TH02&TH03

Location : GYM

...

RATING OF INCOMER	RATING OF ELCB	SL NO	CIR NO	MCB RTG. IN AMPS	CCT WIRE SIZE mm²	ECC WIRE SIZE mm²	ROOM / AREA	CONNECTED LOAD / POINTS														WATT / UNIT	LOAD PER CIRCUIT WATTS			REMARKS
								LTG	STRIP LIGHT	EX FAN	13A SSO	13A TSO	SH S/O	KIT HD	WH	HD	13A SPUR	IND SKT	FCU	CU	ISOL		R	Y	B	
40A TP ISOL	40A, 4P 100mA ELCB-1	1	R1	10	2.5	2.5	PUMP ROOM	7														25	175			LIGHTINGS
		2	Y1				SPACE																			SPACE
		3	B1	10			SPARE															200			200	SPARE
	40A, 4P 30mA ELCB-2	4	R2	20	4.0	4.0	PUMP ROOM				2											200	400			
		5	Y2	20	4.0	4.0	EAF-01 PUMP ROOM													1	370			370		SP ISO. EAF-01
		6	B2				SPACE																			
	40A, 4P 100mA ELCB-3	7	R3	20			SPARE															400	400			
		8	Y3	32	6.0	6.0	ODU-PR-01													1	3630			3630		UVR+TIMER+CONT.
		9	B3	20			SPARE															580			580	SPARE
	40A, 4P 30mA ELCB-4	10	R4	20	6.0	6.0	BOOSTER PUMP SET														1	1100	1100			SP ISO. FOR CWBP
		11	Y4				SPACE																			SPACE
		12	B4	20	6.0	6.0	SUM PIT PUMP SET														1	750			750	20A SP ISO. FOR SUMP PUMP
TOTAL (W)																							2075	4000	1530	

CABLE SIZE: 4C 10 mm² XLPE/SWA/PVC/CU +
1C 10 mm² PVC/CU GY ECC

TOTAL (KW):

7.61

CONSULTANT: ARIF & BINTOAK CONSULTING ARCHITECTS & ENGINEERS, P.O.BOX-3670, DUBAI, UAE, TEL-04 3372888, FAX-04 3370352.

