

LOAD DISTRIBUTION SCHEDULE

Project : GRANDPOLO CLUB & RESORT

Proj. No. : 1857

DB No. : DB-GR

Fed From : DEWA FEEDER

Owner: EMAAR

Consultant: Arif & Bintok consulting architects & engineers

(3-PHASE XR YM)

Area : Dubai South

Plot No. TH-01 ,02 & 03

Location : Guard Room

RATING OF INCOMER	RATING OF ELCB	SL NO	CIR NO	MCB RTG. IN AMPS	CCT WIRE SIZE mm²	ECC WIRE SIZE mm²	ROOM / AREA	CONNECTED LOAD / POINTS														WATT / UNIT	LOAD PER CIRCUIT WATTS			REMARKS
								LTG	EX FAN	13A SSO	13A TSO	SH S/O	KIT HD	WH	HD	20A S/O	IND SKT	FCU	CU	ISOL	R		Y	B		
40A TPN ISOL	40A, 4P 100mA ELCB-1	1	R1	10	2.5	2.5	TOILET/GUARD ROOM/IT RACK	2,1,1,1													25,15,15,10	85				
		2	Y1	10	2.5	2.5	EXTERNAL/PUMPROOM/ ROOF	2,1,2													10,15,15		65			
		3	B1				SPACE																			
	40A, 4P 30mA ELCB-2	7	R2	32	4.0	4.0	GUARD ROOM			2	1										200/400	800				
		8	Y2	20	4.0	4.0	GUARD ROOM				1										400		400			FOR RACK
		9	B2	20	4.0	4.0	ROOF				1									200			200			
		10	R3	20	4.0	4.0	GUARD ROOM				1									200	200				24x7	
		11	Y3	20	4.0	4.0	GUARD ROOM				1									200		200			FACP	
		12	B3	20	4.0	4.0	GUARD ROOM				1									200			200			ACP
	40A, 4P 30mA ELCB-3	13	R4	20	4.0	4.0	PUMP ROOM												1	1,000	1000				BOOSTER PUMP	
		14	Y4	20			SPARE													1,870		1,870				
		15	B4	20	4.0	4.0	PUMP ROOM/EXTERNAL				2									200			400			
	40A, 4P 30mA ELCB-4	16	R5	20	4.0	4.0	GUARD ROOM												1	200	200				GATE BARRIER	
		17	Y5	20	4.0	4.0	GUARD ROOM												1	200			200			GATE BARRIER
		18	B5				SPACE																			
	40A, 4P 100mA ELCB-5	19	R6	20			SPARE													1,000	1000					
		20	Y6	20	4.0	4.0	EAF-GH-01		1										1	100			100			
		21	B6	32	6.0	6.0	FCU-GH-GF-01												1	3,080			3080			
	40A, 4P 30mA ELCB-6	20	R7	20			SPARE													5,000	1667					
		21	Y7						1								1		1667							
																1			1667							
22		B7																								
SUB TOTAL (W)																							4,952	4,502	5,547	

CABLE SIZE: 4C 10 mm² XLPE/SWA/PVC/CU +

1C 10 mm² PVC/CU GY ECC

TOTAL

15.00 kW

CONSUTANT: ARIF & BINTOAK CONSULTING ARCHITECTS & ENGINEERS, P.O.BOX-3670, DUBAI, UAE, TEL-04 3372888, FAX-04 3370352.

